

## [Chapter 15.04 SUBDIVISIONS](#)

---

### **Section 15.04.670 Backfill around structures.**

Backfill around structures shall be placed to the lines shown on the approved drawings, or as directed. After completion of foundation footings and walls and other construction below the elevation of the final grades, and prior to backfilling, all forms shall be removed and the excavation shall be cleaned of all trash and debris. Material for backfilling shall consist of suitable excavated material or borrow sand, gravel, or other suitable material, and shall be placed in layers not exceeding ten (10) inches in uncompacted thickness. Each layer shall be compacted by hand or machine tampers or by other suitable equipment to a density equal to ninety-five (95) percent of maximum dry density as measured by AASHTO-99. (Ord. 5-1988 § 1 (part): Development Code 4-5-3)